



DBLUE BATH WASTE AND OVERFLOW SCHEDULE 40 ROUGH-IN KIT WITH STANDARD TEST KIT

Job Name _____	Item # _____
Location _____	
Engineer _____	Contractor _____
PO # _____	Tag _____
Representative _____	

SPECIFICATIONS

Dearborn Brass Bath Waste & Overflow Schedule 40 PVC Kits are manufactured to strict industry standards. Rough-In Kits contain waste and overflow elbows, spud, test caps, gaskets, and overflow nut. Available in Schedule 40 PVC. Finish options include chrome spud or chrome finished zinc drain spud.

DESCRIPTION

- Made of Schedule 40 Plastic

APPROVALS & LISTINGS

- IAPMO Listed
- Meets ASME A112.18.2-2005/CSA B125.2-2005



PRODUCT SELECTOR

BATH WASTE & OVERFLOW SCHEDULE 40 ROUGH-IN KIT				
✓	Product Number	Description	Carton Quantity	Carton Weight
	P7323	Dblue Rough-In Kit, Schedule 40 - PVC, Chrome Finish Trim	30	33lbs.
	P7323RKZ	Dblue Rough-In Kit, Schedule 40 - PVC with Zinc Spud, Chrome Finish Trim	30	33lbs.

Access BIM/Revit content through www.oatey.com